Material List for Log Complete Packages

DAYLIGHT BASEMENT EXTERIOR WALLS (If Applicable)

- 2X6 Pressure Treated Sills With 6" Foam Sill Sealer
- 2X6 K.D. Spruce Plates And Studs
- 2X10 K.D. Spruce Headers
- ½" CDX Fir Plywood Sheathing With Typar® Air Barrier
- 2X6 #2 Pine Corner Boards (False Corners Are Optional)
- 2X4 #2 Pine Door And Window Trim
- 2X8 Pine Log Siding
- 6 ¼" R-19 Fiberglass Insulation

FLOOR ASSEMBLY

- 2X8 Pressure Treated Sills With 6" Foam Sill Sealer
- Triple 2X10 K.D. Spruce Girder
- Concrete Filled Lally Columns
- 2X10 K.D. Spruce Floor Joists With Double 2X10 K.D. Spruce Box Frame (2X8 on buildings 24' or narrower)
- Joist Hangers As Needed
- 2X10 K.D. Spruce Solid Bridging
- ¾" T&G Fir Underlayment Plywood Sheathing With Construction Adhesive
- 2X12 K.D. Spruce Stair Stringers With 2X10 K.D. Spruce Treads
- Handrail With Brackets

PORCH AND DECK ASSEMBLY

- Triple 2X8 Pressure Treated Girder On 4X6 Pressure Treated Posts
- 2X8 Pressure Treated Joists With Double 2X8 Pressure Treated Box Frame
- Joist Hangers As Needed
- 2X8 Pressure Treated Nailer With Copper Flashing
- 5/4 X 6 Pressure Treated Decking
- 4X10 Dressed Hemlock Porch Roof Girder On 4X6 Pressure Treated Posts
- 2X4 Pressure Treated Railings With 4X4 Pressure Treated Posts And 2X2 Pressure Treated Balusters
- Pressure Treated Stair Material

EXTERIOR WALLS

- 6X8 Kiln Dried D-Shape Pine Logs

- Sikaflex® Adhesive Sealant, Foam Gasket, Pre-cut Hardwood Splines, And 3/8" X 10" Lag Screws With Washers
- 7X7 Pine Inside Corner Posts (If Applicable)
- 2X4 K.D. Spruce Window And Door Bucks
- 2X8 Pine Log Siding For Skirt Board With 15# Felt Paper And Aluminum Flashing (Weather Stop)

SECOND FLOOR: (Models With Stick Framed Gables And Dormers)

- 2X6 K.D. Spruce Plates And Studs
- 2X10 K.D. Spruce Headers
- ½" CDX Fir Plywood Sheathing With Typar® Air Barrier
- 2X6 #2 Pine Corner Boards (False Corners Are Optional)
- 2X4 #2 Pine Window Trim
- 2X8 Pine Log Siding
- 6¼" R-19 Fiberglass Insulation

INTERIOR WALLS

- 2X4 K.D. Spruce Plates And Studs
- 2X6 K.D. Spruce Plates And Studs For Bearing Wall And Plumbing Access Wall
- 2X10 K.D. Spruce Headers

SECOND FLOOR ASSEMBLY

- 6X12 Dressed Hemlock Girder (If Applicable)
- 4X10 Dressed Hemlock Joists (4X8 on buildings 24' or narrower)
- 4X10 Dressed Hemlock Ties (If Applicable)
- Timber Hangers (As Required)
- 2X6 V-Match STK Pine Decking
- 2X12 K.D. Spruce Stair Stringers
- SYP Stair Treads With #2 Pine Risers And Skirt Boards
- 2X6 #2 Pine Railing With 4X4 #2 Pine Posts And Pine Balusters

PORCH GABLES

- 2X4 K.D. Spruce Plates And Studs
- 2X8 Pine Log Siding

ROOF FRAME ASSEMBLY (Varies By Model)

Conventional Rafter System

- 2X12 K.D. Spruce Rafters and Ridge
- 2X6 K.D. Spruce Ceiling Joists

- 2X4 K.D. Spruce Gable Overhangs And Soffit Returns
- 5/8" CDX Fir Plywood Sheathing
- 12" R-38 Fiberglass Insulation With Rafter Vent

Beam Rafter System

- 4X10 Dressed Hemlock Rafters With 4X14 Dressed Hemlock Ridge Beam (4X8 on buildings 24' and narrower)
- 1X V-Match Knotty Pine Ceiling Deck
- 2 Layers Of 2" Foam Insulation
- 2X4 K.D. Spruce Strapping With 2X6 K.D. Spruce Border
- 5/8" CDX Fir Plywood Sheathing

Roof Truss System

- Manufactured Roof Trusses
- 2x4 K.D. Spruce Truss Braces
- 2X4 K.D. Spruce Gable Overhangs
- 5/8" CDX Fir Plywood Sheathing
- 12" R-38 Fiberglass Insulation With Rafter Vent

Porch Rafter System (If Applicable)

- 2x8 K.D. Spruce Rafters
- 2X4 K.D. Spruce Ceiling Joists
- Joist Hangers As Needed
- 2X4 K.D. Spruce Gable Overhangs And Soffit Returns
- 5/8" CDX Fir Plywood Sheathing
- 1X V-Match Knotty Pine Ceiling

ROOF DECK

- 8" Drip Edge, Flashing, 15 lb. Felt Paper, And Ridge Vent
- Ice & Watershield At Eaves And Valleys
- 30 Year Architectural Roof Shingles

EXTERIOR TRIM

- 1X3 Over 1X6 #2 Pine Fascia (Conventional Rafter And Truss)
- 1X6 Over 1X12 #2 Pine Fascia (Beam Rafter)
- 1X4 And 1X8 #2 Pine Eave Soffit With Soffit Vent Strip, And 1X12 #2 Pine Gable Soffit (Conventional Rafter And Truss)
- 1X V-Match Knotty Pine Soffit (Beam Rafter)
- 5/4 X4 #2 Pine Window And Door Trim
- 1X V-Match Knotty Pine Porch Ceiling

EXTERIOR DOORS AND WINDOWS

- Therma-Tru® Steel Insulated Entry Door With Insulated Glass And Lockset
- Pella® 450 Pro-Line® Patio Door Unit With Screen And Muntins (If Applicable)
- Pella® 450 Pro-Line® Aluminum Clad Wood Windows With Screens And Muntins
- Velux® Roof Window Unit With Screen (If Applicable)

INTERIOR FINISH

- 1X V-Match Knotty Pine On Walls And Ceilings

FLOOR COVERING

- 1X Knotty Pine Flooring With Plugs
- 5/8" PTS Plywood Underlayment For Tile Flooring Areas
- ¼" Multi-Ply Underlayment For Vinyl Flooring Areas

INTERIOR DOORS

- 6-Panel Pine Pre-Hung Door Units In Solid Rabbetted Pine Jambs With Hardware
- Pine Panel Bi-Fold Doors With #2 Pine Jamb Stock

INTERIOR TRIM

- 5/4 X4 #2 Pine Head Trim With 1X4 #2 Pine Sides And Bottom
- 1X4 #2 Pine Base Board
- Pine Corner Bead For Outside Corner Trim
- 1X12 #2 Pine Closet Shelving And 1 5/16" Wood Closet Rod With Shelf & Rod

CABINETS, VANITIES AND TOPS

- Kabinart® Hermitage Oak Kitchen Cabinets With Preformed Laminate Countertop
- Kabinart® Hermitage Oak Vanity Cabinet With Palette® Moulded Top

GARAGE (If Applicable)

- 2x4 K.D. Spruce Plates And Studs
- ½" CDX Fir Plywood Sheathing With Typar Air Barrier
- 2X6 #2 Pine Corner Boards (False Corners Are Optional)
- 2X4 #2 Pine Door And Window Trim
- 2X8 Pine Log Siding

- Truss Roof System
- Holmes® Insulated Overhead Doors

MISCELLANEOUS ITEMS

- All Nails And Fasteners
- Outlast™ Q8 Log Oil Preservative Stain
- Shim Shingles